

Sponsorship Fee Credit List for In-Kind Donations

Check Donations to be made by sponsor and total at bottom:

<input type="checkbox"/> Grading and Clearing	\$ 675
<input type="checkbox"/> Footing (Digging Labor)	\$ 370
<input type="checkbox"/> Footing (Pouring Labor)	\$ 128
<input type="checkbox"/> Footing Materials	\$ 1,653
<input type="checkbox"/> Masonry (Labor)	\$ 2,733
<input type="checkbox"/> Masonry (Material)	\$ 2,882
<input type="checkbox"/> Termite Treatment (Warranty Required)	\$ 98
<input type="checkbox"/> Floor Slab (Prep and Pour Labor)	\$ 3,477
<input type="checkbox"/> Floor Slab (Concrete only)	\$ 1,533
<input type="checkbox"/> Ancillary Concrete (Labor)	\$ 234
<input type="checkbox"/> Ancillary Concrete (Materials)	\$ 432
<input type="checkbox"/> Drywall Finishing (Labor)	\$ 730
<input type="checkbox"/> Drywall Materials (including finishing materials)	\$ 905
<input type="checkbox"/> Plumbing Complete (include w/s & excav; no fixtures)	\$ 2,146
<input type="checkbox"/> Plumbing (Fixtures including tub; less DW & GD)	\$ 986
<input type="checkbox"/> Heat & AC System Complete	\$ 3,738
<input type="checkbox"/> Electrical Materials (except panel, breakers and fixtures)	\$ 1,670
<input type="checkbox"/> Electrical Fixtures	\$ 186
<input type="checkbox"/> Electrical Labor	\$ 1,022
<input type="checkbox"/> Vinyl Floor Covering (Materials)	\$ 174
<input type="checkbox"/> Vinyl Floor Covering (Installation – volunteer task)	\$ 0
<input type="checkbox"/> Carpet & Pad (Labor & Material required)	\$ 997
*Color selection must be approved by homeowner	
<input type="checkbox"/> Floor Insulation (Material and Labor – must include installation)	\$ 417
<input type="checkbox"/> Attic Insulation (Material and Labor – must include installation)	\$ 399
<input type="checkbox"/> Wall Insulation (Material and Labor – must include installation)	\$ 548
<input type="checkbox"/> Finish Grading and Seeding:	\$ 1,040
<input type="checkbox"/> Shrubbery (Shrubs, mulch and installation)	\$ 135
<input type="checkbox"/> Total In-Kind Donations listed above:	\$29,308

Total of In-Kind Donations Checked Above _____

These costs are accurate as of February 2009, but are subject to change without notice.

Note: All donated materials must meet performance and design standards established by Habitat. All In-Kind donations must be identified and reported to Habitat 6 weeks prior to the start of volunteer construction using the in-kind donation report form. You can also secure permission from the donor to use donations on another home. Contact Brian Sanders at Habitat for information about other in-kind values. In-kind credit toward Sponsorship Fee can not be made for the following items: roof shingles, interior door hardware, appliances, paint, exterior polystyrene sheathing, electric panel and breakers, and linoleum flooring.

***These credits are against the sponsorship amount, NOT the tax deductible amount. By law Habitat Charlotte cannot assign a value of the gift. It is the donor's responsibility to do so. Donations to the Habitat Re-Store do not count as an in-kind donation.**

Habitat for Humanity Material Specifications

Habitat Charlotte

704 376 2054

fax: 704 342 1797

The following is a list of building materials that Habitat can use on a regular basis. This is not meant to be all-inclusive. Generally, any materials used in the construction of houses will be considered. Since we are building, selling and warranting new houses, we use new materials. Occasionally we will consider a second hand item which is in "like new" condition or is a quality standard above our usual.

1. Bathtub: Fiberglass tub/shower combination: Auqaglass 6076 or equivalent
2. Toilet: Neutral colors: Gerber 21-202 or equivalent.
3. Bathroom vanity: 24", 30", 42" widths: 19" or 21" depths
4. Bathroom sink top: 25", 31" 43": cultured marble tops
5. Bath Faucet: Delta 2522 MPU or equivalent
6. Kitchen Sink: Stainless Steel: 33x22 two compartment: Kingsford 2-3322-4 or equivalent
7. Kitchen Faucet: Delta 400 w/ sprayer or equivalent
8. Water Heater: AO Smith; EES 40 gallon or equivalent
9. Exterior Doors: Prehung 6 panel insulated steel with adjustable threshold; solid wood blocking at the lock location: Sizes: 3-0 x 6-8" (50%)
2-8 x 6-8" (50%)
10. Interior Doors: Prehung, hollow core, 6 panel doors; 442 casing or similar
Sizes: 2-6 x 6-8 (45%)
2-4 x 6-8 (25%)
2-0 x 6-8 (20%)
1-6 x 6-8 (10%)
4-0 x 6-8 Bi-hung (occasional use)
3-0 x 6-8 Bi-hung (2 to 4 per house)
5-0 x 6-8 Bi-hung (1 per house)
11. Windows: Habitat will alter the house to accommodate other sizes of donated windows.
Vinyl, thermopane, low E, double hung with screens
Sizes: 2-8 x 4-4 (8 units per houses)
2-8 x 4-4 Twin (2 per house)
2-8 x 3-0 (2 per house)
12. Kitchen range: 30" Freestanding; 4 burners; 220 volt;
Hotpoint RB536R or similar
Hood Vent
13. HVAC System: Heat Pump; 2 Ton; 13+ Seer; 7.2 HSPF; 5.0 KW auxiliary heat; 240 Volts
latent cooling ratio of 25% or better;
Install according to Duke Power's MAX standards;
Equivalent systems of another type must be approved by HFH.
14. Vinyl siding: .04" thickness: 15 to 20 squares per house
Homeowner will have choice of color.
Related trim and accessories need to be included
15. Shingles: 18 Squares of 25 year asphalt
16. Cabinets: Kitchen/bathrooms
17. Carpeting : 25 ounce continuous filament nylon carpet
½" pad 6 lb. density or better

- 100 yards per house
18. Vinyl flooring: Kitchen, dining room, foyer – VCT Tile
40 yards per house
18. Interior locksets: Kwikset Tylo or equivalent;
typical house:
5 privacy sets
4 passage sets
4 dummy sets
19. Exterior locksets: Schlage or equivalent;
typical house (including shed):
3 entry
3 single cylinder deadbolts
all keyed alike;
20. Electrical See list provided with the electrical information package.
21. Insulation: Floors: R-19 faced fiberglass batts; 15 ½" width
Walls: R-13 or 15 unfaced fiberglass batts; 15 ½" width
Ceilings: R-30 blown fiberglass
22. Concrete: Footings, slab, walks and driveway: amounts are site dependent
23. Masonry All quantities are approximate:
Face brick: 700 Concrete brick: 600
8" block: 500 12" block: 25
4" Solid block: 100 Mortar Mix: 30 bags
Foundation vents: 12